



बुङ्गल नगरपालिका
नगर कार्यपालिकाको कार्यालय
खिरातडी, बझाङ
सुदूरपश्चिम प्रदेश, नेपाल




दर रेट पेश गर्ने सम्बन्धी सूचना
प्रकाशित मिति: २०८१/०२/१७

- १) बुङ्गल नगरपालिकाद्वारा विभिन्न निर्माण व्यवसायी संग तपशिल बमोजिमका निर्माण कार्य गर्नका लागि दर रेट पेश गर्नका लागि यो सूचना प्रकाशन गरिएको छ ।

क्र.स.	विवरण	कुल लागत रकम रु.	दर रेट पेश गर्ने अन्तिम समय	कैफियत
१.	Katai to Kachali Road Maintenance Bungal-01	9,99,869.76	2081/02/23 साँझ ५:०० बजे सम्म	
२.	Bijgada to Khollek Road Maintenance Bungal-03	9,99,625.22	2081/02/23 साँझ ५:०० बजे सम्म	
३.	Manush Pahiro Niyantran Bungal-11	9,94,957.16	2081/02/23 साँझ ५:०० बजे सम्म	
४.	Masonry wall Construction work Back side of Office Building Bungal-07	9,97,670.52	2081/02/23 साँझ ५:०० बजे सम्म	
५.	Sanilya jhad Buda Masani Irrigation Canal Work -05	9,96,583.31	2081/02/23 साँझ ५:०० बजे सम्म	

- २) दर रेट पेश गर्ने निर्माण व्यवसायीले अनिवार्य रूपमा दर रेट पेश गर्ने व्यहोरा सम्बन्धिको लिखित निवेदन सहितको नबिकरण भएको फर्म/कम्पनी दर्ता प्रमाण पत्रको प्रतिलिपी, नबिकरण भएको व्यवसाय दर्ता (निर्माण व्यवसायी ईजाजत पत्र) प्रमाण पत्रको प्रतिलिपी, मु. अ. कर दर्ता प्रमाण पत्रको प्रतिलिपी र आ.व. २०७९/०८० को क. सुत्ता प्रमाण पत्रको प्रतिलिपी संलग्न राखी पेश गर्नु पर्ने छ ।
- ३) माथि उल्लेखित निर्माण कार्यका लागि आवश्यक BOQ फारम यस नगरपालिकाको वेबसाइट www.bungalmun.gov.np बाट download गरि वा बुङ्गल नगरपालिकाको कार्यालयबाट उपलब्ध गर्न सकिने छ ।
- ४) BOQ मा कबोल गरेको रकम अंक र अक्षरमा स्पष्ट रूपमा बुझिने गरि लेखेर पेश गर्नु पर्ने छ । केरमेट गरि पेश भएको दर रेट मूल्यांकनमा समावेश गरिने छैन ।


नि. प्रमुख प्रशासकीय अधिकृत



Bungal Municipality
Office of the Municipality Executive
Khiradi, Bajhang
BOQ

मि. प्रमुख प्रशासकीय अधिकृत

- Road Agency : Bungal Municipality
- Road Name :Katai to Kachali Sadak Marmal Karya
- Location : Bungal - 01

S.N.	Description	Unit	Quantity	Rate		Amount	Remarks	
				In Figures	In Words			
1	Earth Work Excavation	Cum.	24,0118					
2	Gabion Work							
	a. Fabrication of Gabion boxes including rolling, cutting and Weaving							
	3x1x1	Box	26					
	2x1x1	Box	16					
	1.5x1x1	Box	13					
3	b. Assembling of Wire creats/gabion/revetment and placing them in position including stretching, binging them together and tying down lids							
	3x1x1	Box	26					
	2x1x1	Box	16					
	1.5x1x1	Box	13					
4	c. Packing and filling of gabion creates with rubble stone per cum	Cum.	129.5					
Total								
Val@13%								
Grand Total								

In Words:-

Authorised signature :-

Name :-

Designation :-

Firm's Name :-

Office Seal :-

Date :-



Bungal Municipality
Office of the Municipality Executive
Khiradi, Bajhang
BOQ

नि. प्रमुख प्रशासकीय अधिकृत

1. Road Agency : Bungal Municipality
3. Road Name : Bilgada to Khollek Sadak Marnat Karya
Location: Bungal 03

S.N.	Description	Unit	Quantity	Rate		Amount	Remarks	
				In Figures	In Words			
1	Earth Work Excavation	Cum.	23.7218					
2	a. Fabrication of Gabion boxes including rolling, cutting and Weaving	3x1x1						
		2x1x1	Box	26				
		1.5x1x1	Box	16				
		1.5x1x1	Box	13				
	b. Assembling of Wire creats/gabion/revetment and placing them in position including stretching, binnging them together and tying down lids							
	3x1x1	Box	26					
	2x1x1	Box	16					
	1.5x1x1	Box	13					
	c. Packing and filling of gabion creats with rubble stone per cum	Cum.	129.5					
Total								
Val@13%								
Grand Total								

In Words:-

Authorised signature :-
Name :-
Designation :-
Firm's Name :-
Office Seal :-
Date :-



Bungal Municipality

Office of the Municipal Executive

Bijgada, Bajhang

BOQ

मि. प्रमुख प्रशासकीय अधिकृत

Project Name - Masonry Wall Construction Back Side of Ward Office Building
Location - Bungal-7, Bajhang

F/Y: 2080/081

S N.	Description of Work	Unit	Quantity	Rate		Amount	Remarks	
				In Figures	In Words			
1	EW	cum	9.45					
2	Stone Soling	cum	3.02					
3	PCC (1:3:6)	cum	3.05					
4	Stone masonry with c/s mortar (1:6)	cum	59.78					
Total								
Vat@13%								
Grand Total								

In Words:-

Authorised signature :-
Name :-
Designation :-
Firm's Name :-
Office Seal :-
Date :-



BUNGAL MUNICIPALITY
Office of the Municipal Executive
Khiratadi, Bajhang

BOQ

वि. प्रमुख प्रशासकीय अधिकारी

F.V.: 2080/081

Name of Project :- Sanliya Jhad Buda Masani Irrigation Canal Project (2nd)
Location :- Bungal Municipality -05, Bajhang

S.N.	Descriptions	Unit	Quantity	Rate (Rs)		Amount (Rs)	Remarks
				In Figures	In Words		
1	Excavation of Hard clay and soft moorum stones with disposal (up to 10m lid and 1.5m lift)	m ³	13.05				
2	Filling by stones (stone soling) in the foundation and leveling including haulage distance 30m.	m ³	9.90				
3	Concrete of foundation, vertical faces, wall etc. in ratio of 1:2:4 (M15) including supplying of materials and haulage 30m.	m ²	13.20				
4	Cutting, Bending, placing in position & binding of Reinforcement Bars (8mm, dia) for RCC works	kg	499.75				
5	Form Work for Canal Construction	m ²	48.00				
6	Rubble masonry works in (1:6) cement sand mortar (haulage distance upto 10m)	m ³	38.39				
				Sub Total			
				VAT @ 13%			
				Grand Total			

In Words:-

Authorizes signature :-
Name :-
Designation :-
Firm's Name :-
Office Seal :-
Date :-



Bungal Municipality
Office of the Municipal Executive
Bigada, Balhang
BOQ

नि. प्रमुख प्रशासकीय अधिकारी

Name of Project :- Manush Pahiro Nyantzan work (2nd)
Location - Bura pa-11, Balhang.

F/Y: 080/081

S.N.	Description of Work	Unit	Quantity	In Figures	Rate In Words	Amount	Remarks
1	Earthwork in excavation Manually	cum	22.50				
2	Supply of Machine fabricated & mechanically selvaged required different type of gabion boxes (HZC SWG G.I wire) with diaphragms 10*12cm Mesh Size double twist hexazonal mesh with 3.00mm dia mesh wire, 3.90mm dia selvaged wire, 2.4mm dia. lacing wire	Box	25.00				
		Box	18.00				
		Box	23.00				
3	Assembling of wire crests/gabion/revetment and placing them in position including stretching, binding them together and tying down lids (Machine made 100 * 120 box)	Box	25.00				
		Box	18.00				
		Box	23.00				
4	Packing and filling of gabion crests with rubble stones per	cum	145.50				
Total							
Val @ 13%							
Grand Total							

In Words:-

Authorised signature :-

Name :-
Designation :-
Firm's Name :-
Office Seal :-
Date :-